

**SCHEDULE OF BID PRICES
SULPHUR CREEK FISH PASSAGE RESTORATION PROJECT**

1. Mobilization / Demobilization

	Description	Quantity	Unit	Unit Price	Amount
1.01	Mobilization	1	LS		
1.02	Demobilization/Project Closeout	1	LS		
Subtotal Bid Item No. 1					\$

2. Health and Safety

	Description	Quantity	Unit	Unit Price	Amount
2.01	Health and Safety Compliance	1	LS		\$

3. Site Preparation

	Description	Quantity	Unit	Unit Price	Amount
3.01	SWPPP Implementation and Compliance	1	LS		
3.02	Establish Site Access	1	LS		
3.03	Clear and Grub	1	AC		
3.04	Tree Removal	30	EA		
3.05	Temporarily Relocate Mailboxes per USPS Standards (and Replace)	1	LS		
3.06A	Remove Existing Fencing	311	LF		
3.06B	Install New or Replaced Fencing	671	LF		
3.07	Diversion and Dewatering	1	LS		
Subtotal Bid Item No. 3					\$

4. Demolition

	Description	Quantity	Unit	Unit Price	Amount
4.01	Remove Existing Fish Ladder and Concrete, Salvage Existing Riprap	1	LS		
4.02	Hauling and Disposal of Construction Debris	1	LS		
Subtotal Bid Item No. 4					\$

5. Survey and Stakeout

	Description	Quantity	Unit	Unit Price	Amount
5.01	Establish Survey Control, Layout and Project Control Staking	1	LS		\$

6. Roadway and Structures					
	Description	Quantity	Unit	Unit Price	Amount
Roadway					
6.01	Develop Water Supply	1	LS		
6.02	Traffic Control System	1	LS		
6.03	Portable Changeable Message Sign	2	EA		
6.04	Temporary Concrete Washout	1	LS		
6.05	Roadway Excavation	170	CY		
6.06	Class 2 Aggregate Base	42	CY		
6.07	Hot Mix Asphalt (Type A)	62	Ton		
6.08	Place Hot Mix Asphalt Dike (Type A)	70	LF		
6.09	Remove Base and Surfacing	190	YD2		
6.10	Reset Existing Gate	2	EA		
6.11	Delineator (Class 1)	4	EA		
6.12	Relocate Roadside Sign-Two Post	2	EA		
6.13	Vegetation Control (Minor Concrete)	7	YD2		
6.14	Single Thrie Beam Barrier	62.5	LF		
6.15	Return Cap (Type A)	4	EA		
Structures					
6.17	Structure Excavation (Bridge)	74	CY		
6.18	Structure Backfill (Bridge)	42	CY		
6.19	30" Cast-In-Drilled Hole Concrete Piling	222	LF		
6.20	Structural Concrete, Bridge	39	CY		
6.21	Erect Structural Steel (Bridge)	1	LS		
6.22	Bar Reinforcing Steel (Bridge)	12,236	LB		
6.23	Bridge Removal	1	LS		
6.24	Minor Concrete (Curb)	1	CY		
Subtotal Bid Item No. 6					\$
7. Earthwork					
	Description	Quantity	Unit	Unit Price	Amount
7.01	Excavation	2,215	ECY		
7.02	Hauling	2,723	BCY		

7.03	Fill	413	CY		
7.04	QA / QC (survey sub-grade and finish grade)	1	LS		
7.05	Install Log Structures	6	EA		
7.06	Purchase and Install ESM1	1,552	TN		
7.07	Purchase and Install ESM2	708	TN		
7.08	Purchase and Install Bankline Rock	519	TN		
7.09	Purchase and Install Boulders in Channel	56	EA		
7.10	Purchase and Install Bankline Rock Backing	312	TN		
Subtotal Bid Item No. 7					\$

8. Revegetation and Erosion Control

	Description	Quantity	Unit	Unit Price	Amount
8.01	Harvest and Install Live Willow Stakes	168	EA		
8.02	Purchase and Install 1-Gallon Shrubs	91	EA		
8.03	Purchase and Install 5-Gallon Trees	54	EA		
8.04	Foliage Protection Cages	81	EA		
8.05	Purchase and Install Broadcast Seed (Riparian and Upland Seed mix)	25,701	SF		
8.06	One Year Planting, Seeding Maintenance and Invasive Removal	1	LS		
8.07	Straw Wattles (Purchase, Deliver, and Install)	2,503	LF		
8.08	Erosion Control - Stabilized Construction Entrance	3	EA		
8.09	Erosion Control Fabric	3,300	SF		
Subtotal Bid Item No. 8					\$

9. Irrigation

	Description	Quantity	Unit	Unit Price	Amount
9.01	Install Irrigation System	1	LS		
9.02	One Year Irrigation	1	LS		
Subtotal Bid Item No. 9					\$
TOTAL BID \$					